

Date: 17/05/2021

**CORRIGENDUM /ADDENDUM – 02 A**

1. It is notified to all concerned parties that with reference to our **Tender No. IITH/LAN/Wi-Fi/IITRaichr/2021/T003** dated: 09/04/2021 **for the** Providing of LAN/Wi-Fi at IIIT Raichur Campus " the following changes are being made w.r.t. the Tender: -
2. In continuation to point no:06 of **1.2 Networking Labour Components** at Corrigendum/Addendum – 02, the details are as follows.

| 1.2 Networking Labour Components |  |         |     |            |         |
|----------------------------------|--|---------|-----|------------|---------|
|                                  | Labour scope Description   | Unit    | Qty | Compliance | Remarks |
| 7                                | Termination /Fusion Splicing of SMF Optical Fiber cable Including all necessary consumables  | Numbers | 48  |            |         |
| 8                                | Hard soil by digging 1000mm depth & 300 mm width for laying of 6/12 Core SMF OFC cable in HDPE Pipe, placement of OFC metal marker at equal distance of 30 meter long length and turning junction of OFC                                   | Meter   | 500 |            |         |
| 9                                | Concrete Road cut and by digging pit of 1 meter depth laying of 6/12 Core SMF OFC cable in HDPE Pipe along and closure of pit with necessary cementing of road to original condition, Placement of OFC metal marker on either side of road | Meter   | 30  |            |         |
| 10                               | Laying of 25/32/50 MM PVC Conduit/Casing & casing/flexible pipe Approval: Under ISI/ISO make FRLS graded 2mm thick with required accessories   | Meters  | 890 |            |         |
| 11                               | Mounting / installation of 19" 12 U Network Rack to wall   | Numbers | 3   |            |         |
| 12                               | Mounting / installation of 19" 42 U Network Rack to wall (Rack details given in tender)  | Numbers | 1   |            |         |
| 13                               | Rodent protection with metal mesh & glass wool wherever openings are there in Network Rack   | Numbers | 4   |            |         |
| 14                               | Construction of 2ft X 2ft Main Hole Chamber with Bricks, Sand, Concrete, Top Cover etc   | Numbers | 10  |            |         |
| 15                               | Cat 6 Cable /points testing, patching printed labels on both end cables/face plate/jack panel & turn style labels for patch cord both ends   | Job     | 1   |            |         |

|    |   |     |   |  |  |
|----|---|-----|---|--|--|
| 16 | OFC testing with OTDR, Labelling of OFC cables & LIU, patching with SC to LC patch cords between LIU & Media converter or between LIU's | Job | 1 |  |  |
|----|---|-----|---|--|--|

3. All other terms and conditions of the tender remain unchanged. Bidders, who have already submitted their bids prior to issue of this corrigendum need to submit again.